Add Beauty and Value to your Home.

Ornamental

Railings & Columns

THE VILLAGE IRONSMITH™
We've Done the Hard Work for You...
LL BUILDING PRODUCTS INC.®

PROJECT LAYOUT GUIDE

On the grid, sketch the lines of your new railings and columns. Mark the location of all posts and columns. Count the number of rail sections for each length, columns and posts and enter on Shopping Worksheet.

- Add one Floor Flange for each post needed to complete the job.
- If mounting on Wood, use Lag Screws (LS100).
- If Concrete, use Masonry Anchors (MA100). One package of each per post.
- Add the connectors (one package of connectors per rail section).

Note: FOR ALL RAIL SECTIONS
All Rails are sold in 4' and 6' sections and can be cut to length.

Note: FOR COLUMNS
If columns are part of your installation, enter the appropriate number of flat and/or corner columns and sockets on the worksheet.
Column Sockets needed: Flat Columns = 1 package.
Corner columns = 2 packages.

ON-CENTER SPACING FOR POSTS

	Classic® Rails using NP125 posts	Metropolitan™ Rails using MP125 posts
4 ft. Rails	4 ft. 1 1/4 in.	4 ft. 1 1/4 in.
6 ft. Rails	6 ft. 1 1/4 in.	6 ft. 1 1/4 in.

Widths of columns are 9 inches



© 2007 LL Building Products Inc.

GAF®
GAF MATERIALS CORPORATION